

THE FOLLOWING ARE THE MINIMUM STANDARDS FOR COMPLIANCE WITH HEALTH DEPARTMENT REQUIREMENTS. THE G.C. AND KEC CONTRACTOR SHALL COMPLY WITH THESE MINIMUM STANDARDS, DRAWINGS AND SPECIFICATIONS.

1. A CONCRETE SLAB IS PROVIDED FOR TRASH, GARBAGE, AND GREASE CONTAINER. IF WALLS ENCLOSE THIS AREA, THE INTERIOR WALL SURFACE WILL BE SMOOTH, SEALED AND WASHABLE (i.e., PLASTERED SMOOTH AND PAINTED, ETC.)
2. ALL FOOD-RELATED AND UTENSIL-RELATED EQUIPMENT SHALL MEET OR BE EQUIVALENT TO SANITATION STANDARDS ESTABLISHED BY AN AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) ACCREDITED PROGRAM.
3. ALL FLOOR MOUNTED EQUIPMENT WILL BE INSTALLED ON MINIMUM 6" SANITARY LEGS, CASTERS OR COMPLETELY SEALED IN POSITION ON A 4" HIGH CURB WITH CONTINUOUSLY COVERED BASE. COUNTERTOP EQUIPMENT WILL BE ON 4" SANITARY LEGS OR SEALED TO THE COUNTER UNLESS READILY MOVABLE.
4. FOR ALL SELF-SERVICE SODA, ICE AND OTHER DISPENSERS WHERE REFILLS ARE PROVIDED THEY MUST BE PUSH BUTTON TYPES, OR LEVER TYPE WHERE THE LEVER CONTACTS THE CONTAINER AT LEAST ONE INCH BELOW THE RIM.
5. ANY OPERABLE WINDOWS, VENT OPENING, OR OTHER SIMILAR OPENINGS MUST BE PROVIDED WITH TIGHT FITTING SCREENS OF MINIMUM 16 MESH TO THE INCH. WINDOWS SHALL BE FIXED AT FOOD PREP, UTENSIL-WASHING, OPEN FOOD AND UTENSIL STORAGE AREAS.
6. ALL EXTERIOR DOORS SHALL OPEN OUTWARD, BE SELF-CLOSING AND TIGHT FITTING.
7. BI-FOLD, FRENCH, ACCORDION STYLE AND ROLL-UP DOORS CANNOT OPEN INTO THE FOOD PREP, UTENSIL WASHING OR UNPACKAGED FOOD SERVICE AREAS.
8. TOILET ROOM AND DRESSING ROOM DOORS MUST BE SELF-CLOSING AND TIGHT FITTING.
9. DELIVERY DOORS SHALL HAVE AIR CURTAIN FANS THAT SPAN THE WIDTH OVER THE DOOR. THE FAN MUST ACTIVATE VIA A MICROSWITCH PROVIDING A MINIMUM VELOCITY OF 1600 FPM MEASURED 3 FEET ABOVE THE GROUND.
10. A MINIMUM OF 10 FOOT-CANDLES OF LIGHT MEASURED 30" OFF FLOOR SHALL BE PROVIDED IN WALK-IN REFRIGERATED STORAGE AND DRY STORAGE AREAS.
11. A MINIMUM OF 20-FOOT CANDLES OF LIGHT SHALL BE PROVIDED WHERE FOOD, FRESH PRODUCE OR PRE-PACKAGED ITEMS ARE PROVIDED FOR CONSUMER SELF-SERVICE AND SOLD OR OFFERED FOR CONSUMPTION INSIDE EQUIPMENT, IN AREAS USED FOR HAND WASHING, WAREWASHING, UTENSIL STORAGE, AND TOILET ROOMS.
12. A MINIMUM OF 50 FOOT-CANDLES OF LIGHT MEASURED 30" OFF FLOOR SHALL BE PROVIDED WHEN WORKING WITH FOOD, UTENSILS, EQUIPMENT SUCH AS KNIVES, SLICERS, GRINDERS, AREAS WHERE EMPLOYEE SAFETY IS A FACTOR AND IN ALL AREAS DURING PERIODS OF CLEANING.
13. SHATTER SHIELDS SHALL BE PROVIDED FOR ALL LIGHTS ABOVE FOOD PREPARATION, WORK, AND STORAGE AREAS.
14. ALL WAREWASHING SINKS TO HAVE 3 COMPARTMENTS THAT ARE A MINIMUM SIZE OF AT LEAST 18"X18"X12" DEEP (OR 16"X20"X12" DEEP) WITH A MINIMUM 18" DRAINBOARD AT EACH END. IF AGAINST A WALL, IT MUST HAVE AN 8" INTEGRAL BACKLASH. HOWEVER, IT MUST BE CAPABLE OF ACCOMMODATING THE LARGEST UTENSIL TO BE WASHED. A WAREWASHING MACHINE DOES NOT SUBSTITUTE FOR SINK REQUIREMENT. 3 OR 4 COMPARTMENT BAR SINKS TO BE AT LEAST 12"X12"X10" DEEP (OR 10"X14"X10" DEEP) WITH A MINIMUM 18" DRAINBOARD AT EACH END.
15. ALL SINKS SHALL HAVE SPOUT(S) CAPABLE OF REACHING EACH COMPARTMENT.
16. FOOD PREP SINK COMPARTMENT(S) TO BE AT LEAST 18"X18"X12" DEEP (OR 16"X20"X12" DEEP) WITH A MINIMUM 18" DRAINBOARD. SEPARATE FOOD PREP SINKS SHALL BE PROVIDED FOR MEATS AND PRODUCE.
17. A SEPARATE WET WASTE DUMP FIXTURE SHALL BE PROVIDED FOR DISPOSAL OF DRINK OR ICE WASTE.
18. EACH HAND WASHING SINK MUST HAVE PERMANENTLY MOUNTED SINGLE-SERVICE SOAP AND PAPER TOWEL DISPENSERS.
19. THE HOT WATER HEATER WILL BE A COMMERCIAL TYPE CAPABLE OF CONSTANTLY SUPPLYING HOT WATER AT A TEMPERATURE OF 120° F TO ALL SINKS. IN SIZING THE WATER HEATER, THE PEAK HOURLY DEMAND FOR ALL SINKS, ETC., ARE ADDED TOGETHER TO DETERMINE THE MINIMUM REQUIRED RECOVERY RATE.
20. ALL LAVATORIES OR HAND SINKS WILL HAVE A COMBINATION FAUCET OR PREMIXING FAUCET CAPABLE OF SUPPLYING WATER TEMPERED TO 100°-108°F. SELF-CLOSING OR METERED FAUCET TO PROVIDE AT LEAST 15 SECONDS OF WATER WITHOUT REACTIVATION.
21. ALL PLUMBING, ELECTRICAL AND GAS LINES SHALL BE CONCEALED WITHIN THE BUILDING STRUCTURE TO GREAT AN EXTENT AS POSSIBLE. ALL EXPOSED CONDUITS, PLUMBING, ETC. SHALL BE INSTALLED AT LEAST 6" OFF FLOOR AND 3/4" FROM WALLS USING STANDAUFF BRACKETS.
22. CONDUITS, PLUMBING OR PIPING CANNOT BE INSTALLED ACROSS ANY AISLE WAY, TRAFFIC AREA OR DOOR OPENING.
23. MULTIPLE RUNS OR CLUSTERS OF CONDUIT OR PIPELINES SHALL BE FURRED IN OR ENCASED IN AN APPROVED SEALED ENCLOSURE.
24. ALL LIQUID WASTE SHALL BE DRAINED BE MEANS OF INDIRECT WASTE PIPES INTO A FLOOR SINK. FLOOR SINKS ARE TO BE INSTALLED FLUSH WITH THE FINISHED FLOOR SURFACE AND HAVE SUITABLE EASILY REMOVABLE SAFETY COVER GRATES.
25. FLOOR SINK TO BE 50% EXPOSED WHEN NO ACCESS IS PROVIDED FOR CLEANING OR BE IN LINE WITH THE FRONT FACE OF ELEVATED FREESTANDING EQUIPMENT.
26. APPROVED BACKFLOW PREVENTION DEVICES SHALL BE PROPERLY INSTALLED UPSTREAM OF ANY POTENTIAL HAZARD BETWEEN THE POTABLE WATER SUPPLY AND A SOURCE OF CONTAMINATION. HOSES SHALL NOT BE ATTACHED TO A FAUCET OR HOSE BIBB UNLESS AN APPROVED BACKFLOW PREVENTER IS PROVIDED.
27. WATER SUPPLY TO CARBONATORS SHALL BE PROTECTED BY AN APPROVED REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTER. THE RELIEF VALVE SHALL DRAIN INDIRECTLY TO SEWER WITH A LEGAL AIR GAP.
28. FOR CLEANING FLOOR MATS, THE JANITORIAL SINK SHALL BE A MINIMUM 24" BY 36" FLOOR-MOUNTED TYPE. MOPS SHALL BE PLACED IN A POSITION THAT ALLOWS THEM TO AIR-DRY WITHOUT SOILING WALLS, EQUIPMENT, OR SUPPLIES.
29. THE JANITORIAL SINK FAUCET WILL HAVE A THREADED OUTER LIP FOR HOSE ATTACHMENT AND AN APPROVED BACKFLOW PREVENTION DEVICE. NO CHEMICAL DISPENSING SYSTEMS OR SHUTOFF VALVES TO BE ATTACHED TO MOP SINK FAUCET OUTLET UNLESS A "SIDEKICK" PLUMBING DEVICE IS INSTALLED).
30. NO CONDENSATE OR WASTEWATER INCLUDING HVAC WILL DRAIN INTO THE JANITORIAL SINK.
31. GREASE TRAP TO BE LOCATED OUTSIDE THE FOOD SERVICE ACTIVITY AREA. FLUSH WITH THE FINISHED FLOOR WHEN INDOORS. LOCAL WASTEWATER DISTRICT OR BUILDING DEPARTMENT TO BE CONTACTED FOR GREASE REMOVAL REQUIREMENTS.
32. FLOOR DRAINS SHALL BE INSTALLED IN FLOORS THAT ARE WATER-FLUSHED FOR CLEANING AND IN AREAS WHERE PRESSURE SPRAY METHODS FOR CLEANING EQUIPMENT ARE USED, IN RESTROOMS, JANITORIAL ROOMS, SCULLERIES, AND AT BARS WITH WAREWASHING. FLOOR SURFACES IN AREAS PURSUANT TO THIS SHALL BE SLOPED 1.50 TO THE FLOOR DRAINS.
33. ADEQUATE VENTILATION SHALL BE PROVIDED TO ALL TOILET ROOMS, JANITOR CLOSETS WITH MOP SINKS, INDOOR TRASH ROOMS AND IN DRESSING/ CHANGING ROOM(S).
34. THE FLOOR FINISH SHALL HAVE A SMOOTH SURFACE UNDER ALL EQUIPMENT AND WALKWAYS WILL HAVE A LIGHT TEXTURE ONLY.
35. THE PAINT USED ON WALLS AND CEILINGS OF ALL KITCHEN, FOOD PREPARATION, WORK, STORAGE AREAS SHALL BE GLOSS OR SEMI-GLOSS ENAMEL. FINISH MATERIAL SHALL BE LIGHT COLOR IN FOOD PREP AREAS FOR EASY CLEANING.
36. PRIOR TO INSTALLATION, SAMPLES OF FINISHES SHALL BE SUBMITTED TO ENVIRONMENTAL HEALTH FOR APPROVAL AS NEEDED.
37. COLD STORAGE ROOMS SHALL BE PROVIDED WITH A SECTION OF SHELVING INSTALLED TO HOLD SHALLOW COOL DOWN PANS - NOT TO EXCEED 4" IN HEIGHT. SPACE BETWEEN SHELVING TO BE AT LEAST 8" HIGH.
38. BACKUP DRY STORAGE SHELVING SHALL BE A MINIMUM OF 6 LINEAR FEET (MEASURED WITH TIERS) OR 25% OF KITCHEN, FOOD PREP, AND WORK AREAS, WHICHEVER IS GREATER. SHELVING SHALL BE AT LEAST 18 INCHES DEEP AND START A MINIMUM SIX INCHES OFF THE FLOOR SURFACE.
39. SHELVING OVER WET AREAS (SINKS, MOP SINKS ETC.) AND FOOD PREP SURFACES SHALL BE METAL.
40. ALL SEAMS, GAPS, OPENINGS SHALL BE PROPERLY SEALED PER CODE.
41. ALL EMPLOYEE RESTROOMS SHALL BE PROVIDED WITH SOAP & TOWEL DISPENSERS.

1. SEISMIC DETAILS, ENGINEERING, SUPPLY AND INSTALLATION ARE NOT INCLUDED BY FOOD SERVICE CONSULTANT OR KITCHEN EQUIPMENT SUPPLIER.

1400 N AVENUE
NATIONAL CITY, CA 91950

NOTE:
TRASH DUMPSTER LOCATION. ALL ENCLOSURE
WALLS TO BE SEALED, SMOOTH AND PAINTED
WITH SEMI-GLOSS ENAMEL OR EQUAL AND WITH
70% REFLECTANCE

[illegible]

©SGPA 2025

PREPARED FOR THE

FOOD SERVICE TITLE SHEET AND FINISH SCHEDULE

NATIONAL SCHOOL DISTRICT
NATIONAL CITY, CALIFORNIA

PREPARED BY
SGPA ARCHITECTURE
AND PLANNING

SUBMITTALS / REVISIONS

#	ISSUE	DATE
	DSA SUBMITTAL V1	03/19/2025
	DSA SUBMITTAL V2	04/30/2025

**BID SET 5/1/2025
NOT FOR
CONSTRUCTION
PROJECT STILL IN
REVIEW**

PROJECT NO. 2239-E-02

SHEET NO.

K-T

DSA

CONSULTANT

STAMM